

E Cypress And Fifth St Water Main Installation

- 1) Provide Sunshine State One Call locates.
- 2) Provide any maintenance of traffic set up that may be needed per Florida Department of Transportation (FDOT) or Lee County Department of Transportation (LCDOT) specs.
- 3) Locate and expose all existing utilities that may be in conflict.
- 4) Provide and use all shoring devices needed to protect the edge of the road and any other existing structures or utilities.
- 5) Schedule all work with either Daniel Labelle, Water Distribution Manager, or Matt Stephens LCU Supervisor, and Robert Lowery, Lee County Utilities (LCU) Inspector.
- 6) Hand deliver all Boil Water Notices to any customers that will be out of water, allowing at least 48 hours of notice.
- 7) Collect and deliver bacteriological samples to the Lee County Laboratory or Department of Health and provide LCU with 2 Consecutive days of passing results.
- 8) Provide all restoration that is needed to restore the site back to its original state as per LCDOT or FDOT specs. This includes Asphalt, Concrete and Landscaping, ECT. LCU inspector and or LCU Management reserve the right to have contractor redo any job that is not up to LCU standard.
- 9) Provide all R.O.W. permits required.
- 10) All work will be completed in compliance with L.C.U. specs.
- 11) Provide a set of asbuilts, at the time of bacti. Sampling.
- 12) Provide documentation of water main flushing, and pressure testing with L.C.U. inspector on site.
- 13) Provide survey for Lee County R.O.W.

- 14) There will be a mandatory preconstruction meeting at a location to be determined.
- 15) Provide L.C.U. with a preconstruction video detailing the existing site conditions.
- 16) Obtain written permission from property owners where any materials are to be stored, equipment set up, or if work is to be done outside of the Lee County R.O.W. or easement.
- 17) Follow appropriate regulations that pertain to dewatering and the discharge of all water from any excavation.
- 18) Tracer wire must be installed with the new water main.
- 19) Bid this project per L.C.U. provided plans.
- 20) Project must be completed within 90 days of receiving the purchase order.
- 21) Install approximately 2000' of 12" HDPE. All 12" HDPE will be supplied by LCU. Contractor to supply all other materials. This job will include, full bore flush, pressure test and chlorinate, tie in's, Fire Hydrants and Water services, Transferring of water services once the new water main is accepted, replace all meter boxes with new, all restoration's, ect. Please see attached plans for job details. LCU will make decision to keep any and all old meter box lids.


Company Name: CARAWA CONST OF SW FL INC

Signature: *Kenneth Cal*

Contacts: Daniel Labelle, Water Distribution Manager, L.C.U. 239-839-5421
Matt Stephens, Water Distribution supervisor, L.C.U. 239-322-4333
Robert Lowery, Inspector, L.C.U. 239-822-9506

\$ 195,225.⁰⁰

One Hundred Ninety Five Thousand Two Hundred Twenty Five \$ ⁰⁰/₁₀₀



Boyd Irrigation, Inc.
 8050 Bayshore Road
 North Fort Myers, FL 33917
 Phone: 239-543-1616
 Fax: 239-543-4676
 klake@boydirrigation.com

Mailing Address:
 PO Box 2509
 Ft. Myers, FL 33902

PROPOSAL

Submitted To: Lee County Utilities Attn: Matt Stephens, Utilities Supervisor
 5180 Tice St., Fort Myers, FL 33905

Phone: 239-533-8272

Cell: 239-322-4333

Email: MStephens2@leegov.com

Project: E Cypress and Fifth St Water Main Installation

We will complete the E Cypress and Fifth St Water Main Installation per provided drawings and attached Scope of Work for the lump sum of

TOTAL LUMP SUM AMOUNT = \$236,744.00

TOTAL: Two Hundred Thirty-Six Thousand Seven Hundred Forty-Four and No/100-----Dollars

*** E Cypress and Fifth St Water Main Installation Scope of Work Items (1) – (21) Received, Acknowledged, and Attached***

Standard Proposal Notes

The following are our assumptions and we respectfully request that you consider them an integral part of our proposal and contract. Boyd Irrigation, Inc. will perform all work in accordance with the drawings and specifications as referenced above and complete the project in a substantial, workmanlike manner for the amount agreed upon. Payment is due within 30 days of invoice date. Any alteration or deviation from the specifications will become an extra charge over the estimated amount and will be executed upon written orders only. Strikes, accidents or delays beyond our control will void or necessitate change to our agreement. The Owner is to carry fire, tornado, and other necessary insurance on the work. Boyd Irrigation, Inc. will be responsible for workers' compensation and public liability insurance on the work. This proposal may be withdrawn if not accepted within thirty (30) days. Exclusions not included in our proposal and contract follows:

Boyd Irrigation, Inc. is not responsible for the following:

- Layout or surveying costs;
- No testing costs;
- All piping to stop 5 ft. from building envelope;
- All connections to buildings will be done by others;
- Certified As-Builts;
- No off-site removal of rock, muck, or other unsuitable materials;
- No excavation or replacement of unsuitable fill;
- Not responsible for damage to private utilities not located by owner;
- No impact, connection or water use fees;
- No bonds or permits not explicitly stated, except firelines;
- No rock excavation, blasting or trenching;
- No sod, seed, mulch or landscaping restoration;
- No maintenance of traffic or traffic control costs;
- No concrete, asphalt or pavement marking restoration;
- No erosion or sediment control or testing for dewatering;
- No NPDES or environmental monitoring, reports and permits.

Submitted By: Jeffrey D. Boyd, President

ACCEPTANCE OF PROPOSAL

We accept the above prices, specifications and conditions. Boyd Irrigation, Inc. is authorized to do the work specified and payment will be made as outlined above.

Owner's Representative

Printed Name, Title

Date

Please sign above and email all pages to klake@boydirrigation.com or fax all pages to Boyd Irrigation, Inc. at 239-543-4676.

*State of Florida Certified General Contractor #CGC1517865 & Certified Underground Utility & Excavation Contractor License # CUC 056896
 Contractor V Florida State Fire Marshal License #10524900012000*

