



County Project Authorization (CPA) Form

Contract Name: Purchase of Daikin HVAC Equipment and Installation CPA Number: 5
Project Name: Lee County Justice Center Tower Air Handler Unit Fan Array Replacement Contractor's Name: Carroll Air Systems, Inc.

Contract Number:	8082	Total Project Amount:	\$ 200,630.00
Solicitation Number:	PB180483JJB	Account Number:	40896300100
Lee County Project Manager:	Marco Dano	Project Number:	408963
Fiscal Staff:	Beverly Dearborn	Request Date:	3/19/2019

Description / Scope of Work (include location):

Vendor shall perform work detailed on Vendor's Proposal No. R150505-FL-30194 attached and labeled as "Attachment 1"

Length of time to Substantial Completion from Notice to Proceed (in calendar days): 180
Length of time to Final Completion from Notice to Proceed (in calendar days): 210
Liquidated Damages amount to be assessed per calendar day after Substantial Completion (if applicable): \$760


Contractor Signature (Print & Sign Name)

pcarroll@carrollair.com

Contact E-mail Address

04/17/2019

Date Accepted

813-879-5790

Contact Phone Number

Lee County Procurement Approval

Lee County Authorized Approval

Date Accepted

Date Accepted

Lee County Board of County Commissioners - Procurement Management

1500 Monroe Street - Fort Myers, FL 33901

PO Box 398 - Fort Myers, FL 33902-0398

Phone: (239) 533-8881



6360 Arc Way Suite 4
Ft. Myers, FL 33966
Phone: (239) 939-5553
Fax: (239) 939-5549

PROPOSAL

DATE: 03-13-19

Certified Proposal Number: R150505-FL-18590

Proposal is in accordance with Region 4 ESC contract #R150505 available via National IPA.



PROPOSAL TO: Lee County Board of Commissioners
SUBJECT: LCJC Tower
AHU-1RA Fan Array Replacement

We are pleased to offer the following equipment per pricing of the NIPA contract; F.O.B. Destination, net 45 days, terms subject to credit approval, **sales tax is not included in the pricing**. Pricing valid for thirty (30) days from date of proposal. The billing may be split between Carroll Air Systems, Inc. and the manufacturer.

AHU-1RA RETURN AIR FAN ARRAY EQUIPMENT SCOPE OF SUPPLY

Item	Description	Material Supplied By	Qty
1	Provision of (1) Q-PAC Array with: <ul style="list-style-type: none"> - (9) SWSI Direct Drive Plenum Fans with EC Motor <ul style="list-style-type: none"> • (1) 9-PAC - (1) Single point power panel with non- fused disconnect, control Terminals , and HOA switch with Manula speed adjustment.Panel to be field mounted, wiring not to be provided. - Motor protection built in to each fan assembly - Bulkhead assembly - Structural support along the perimeter of bulkhead is to be field provided. 	CAS	(1) 9-PAC

AHU-1RA SUPPLY AIR FAN ARRAY EQUIPMENT SCOPE OF SUPPLY

Item	Description	Material Supplied By	Qty
1	Provision of (1) Q-PAC Array with: <ul style="list-style-type: none"> - (18) SWSI Direct Drive Plenum Fans with EC Motor <ul style="list-style-type: none"> • (1) 18-PAC - (1) Single point power panel with non-fused disconnect, control terminals, and HOA switch with manual speed adjustment.Panel to be field mounted, wiring not to be provided. - Motor protection built in to each fan assembly - Bulkhead assembly - Structural support along the perimeter of bulkhead is to be field provided 	CAS	(1) 18-PAC

INSTALLATION Scope

AHU Fanwall Retrofit: -Remove the supply and return fan motors and Blowers

-Remove inlet cones

-Install supply and return Q-Pac fan walls

-Wire in the line voltage to the new motors

-Install control wires from the existing VFD's to the EC controllers

-Startup system and check operation

-Pre and post Static readings on AHU

-Remove all material and trash from the BLDG

-Work to be done after hours (weekend work)

-Work to be done over multiple weekends or a holiday/ long weekend

-Will have the machine back online for business days

-We exclude the following items:

-Roofing, painting, patching, concrete slabs and supports, concrete cutting and patching, asphalt cutting and patching, plumbing, ceiling and electrical work including disconnect switches and starters unless specified to be furnished by the equipment manufacturers

FAN ARRAY PRICING

The total project price is **\$200,630.00**, delivered to the customer specified jobsite address. Includes field supervision for 2 days. Includes Payment and Performance Bond. The pricing does not include site delivery detention costs, applicable taxes, duties, fees, startup, labor warranties, or other related charges. Standard lead time, included in the base cost, for us to receive the Q-PAC fans is 6-10 weeks (does not include our install time). This quote is valid for 30 days.

SUBMITTED BY:

Andrew Kee

Carroll Air Systems, Inc.

Sales Manager-SW Florida/Florida Keys

6360 Arc Way Suite 4

Ft. Myers, FL 33966

Phone: (239) 939-5553

Fax: (239) 939-5549

Cell: (239) 209-0520

Email: akee@carrollair.com

Contact: Andrew Kee @ (239) 939-5553 for information and pricing pertaining to this scope and proposal. **Thank You.**
Cell Phone: (239) 209-0520. Fax: (239) 939-5549. E-mail: akee@carrollair.com